





Publication Year	2008
Acceptance in OA	2024-06-24T10:13:50Z
Title	TV Tests: Contingency procedure due to drain currents overlimit
Authors	GREGORIO, Anna, CUTTAIA, FRANCESCO, MENNELLA, ANIELLO
Handle	http://hdl.handle.net/20.500.12386/35219
Volume	PL-LFI-PST-PR-027



TITLE:	TV Tests: Contingency procedure due to drain currents overlimit	
DOC. TYPE:	PROCEDURE	
PROJECT REF.:	PL-LFI-PST-PR-027	PAGE: I of IV, 7
ISSUE/REV.:	1.0	DATE: June 10th 2008

Prepared by	A. GREGORIO A. MENNELLA F. CUTTAIA On behalf of LFI IOT LFI Project System Team	Date: June 10 th 2008 Signature: 
Agreed by	C. BUTLER LFI Program Manager	Date: June 10 th 2008 Signature: 
Approved by	N. MANDOLESI LFI Principal Investigator	Date: June 10 th 2008 Signature: 



DISTRIBUTION LIST

Recipient	Company / Institute	E-mail address	Sent
N. MANDOLESI	IASF/INAF – Bologna	mandolesi@iasfbo.inaf.it	Yes
R.C. BUTLER	IASF/INAF – Bologna	butler@iasfbo.inaf.it	Yes
M. BERSANELLI	UNIMI – Milano	marco.bersanelli@mi.infn.it	Yes
D. MENNELLA	UNIMI- Milano	Aniello.Mennella@fisica.unimi.it	Yes
M. BALASINI	TAS-I	maurizio.balasini@thalesalieniaspace.com	Yes
R. SILVESTRI	TAS-I	roberto.silvestri@thalesalieniaspace.com	Yes
P. LEUTENEGGER	TAS-I	paolo.leutenegger@thalesalieniaspace.com	Yes
M. MICCOLIS	TAS-I	maurizio.miccolis@thalesalieniaspace.com	Yes
G. CAFAGNA	TAS-I	gaetano.cafagna@thalesalieniaspace.com	Yes
L. PEREZ CUEVAS	ESA	leticia.perez.cuevas@esa.int	Yes
O. PIERSANTI	ESA	Osvaldo.Piersanti@esa.int	Yes
S. MADDEN	ESA	Sean.Madden@esa.int	Yes
B. GUILLAUME	ESA	Bernard.Guillaume@esa.int	Yes
A. COLOMBO	ESA	Andrea.Colombo@esa.int	Yes
J.P. CHAMBELLAND	TAS-F	Jean-philippe.Chambelland@thalesalieniaspace.com	Yes
B. COLLAUDIN	TAS-F	Bernard.Collaudin@thalesalieniaspace.com	Yes
P. RIHET	TAS-F	Patrick.Rihet@thalesalieniaspace.com	Yes
N. SEVILLE	TAS-F	Norbert.Seville@thalesalieniaspace.com	Yes
F. CUTTAIA	IASF/INAF – Bologna	cuttaia@iasfbo.inaf.it	Yes
LFI System PCC	IASF/INAF – Bologna	lfispcc@bo.iasf.cnr.it	Yes



TV Tests: Contingency procedure due to drain currents overlimit

Document No.: PL-LFI-PST-PR-027
Issue/Rev. No.: 1.0
Date: June 10th 2008
Page: III

CHANGE RECORD

Issue	Date	Sheet	Description of Change	Release
1.0	June 2008		First issue of Document	



TABLE OF CONTENTS

1	ACRONYMS	1
2	INTRODUCTION.....	2
2.1	PURPOSE AND SCOPE	2
3	APPLICABLE AND REFERENCE DOCUMENTS.....	3
3.1	APPLICABLE DOCUMENTS.....	3
3.2	REFERENCE DOCUMENTS.....	3
4	GENERAL REQUIREMENTS	4
4.1	RESPONSIBILITIES	4
4.2	ENVIRONMENTAL CONDITIONS	4
4.3	OPERATIONAL CONSTRAINTS AND RECOMMENDATIONS	4
5	DRAIN CURRENTS OVERLIMITS.....	5



1 ACRONYMS

AIV	Assembly, Integration, Verification
ASW	Application Software
BEM	Back End Module
BEU	Back End Unit
CCS	Central Check-out System
CDMU	Central Data Management Unit
DAE	Data Acquisition Electronics
DPU	Digital Processing Unit
EGSE	Electrical ground Support Equipment
FEM	Front End Module
FPT	Focal Plane Temperature
FPU	Focal Plane Unit
I-EGSE	Instrument EGSE
ILT	Instrument Level Test
IOT	Instrument Operation Team
IST	Integrated Satellite Test
LNA	Low Noise Amplifier
OBC	On Board Clock
P/S	Phase Shifter
RAA	Radiometer Array Assembly
RCA	Radiometer Chain Assembly
REBA	Radiometric Electronic Box Assembly
S/C	Spacecraft
SCE	Sorption Cooler Electronics
SCOE	Spacecraft Control and Operation System
SCS	Sorption Cooler System
SFT	Short functional Test
SPU	Signal Processing Unit
SUSW	Start- Up Software
SVM	Service Module
TBC	To Be Confirmed
TBD	To Be Defined
TBW	To Be Written
TC	Telecommand
TM	Telemetry
UFT	Unit Functional Test
WFT	Warm Functional Test



2 INTRODUCTION

This document has been issued in the frame of ASI contract that has been released for the activities of Planck-LFI Phase E2

2.1 Purpose and Scope

Scope of this document is to give a description of the steps to be performed when a possible contingency action is required, in particular when unexpected features on the drain currents value is observed.

The test sequence will be applied if necessary while the LFI is in cryogenic condition under vacuum inside the CSL facility.

The test is scheduled respect to TAS-F plan and test specification.



3 APPLICABLE AND REFERENCE DOCUMENTS

3.1 Applicable Documents

- [AD1] Herschel/Planck Instrument Interface document Part A
SCI-PT-IIDA-04624 Issue 3.3
- [AD2] Herschel/Planck Instrument Interface document Part B
SCI-PT-IIDB-04142 Issue 3.1
- [AD3] Herschel/Planck Instrument Interface document Part B
SCI-PT-IIDB-04142 Issue 3.1, Annex 3, ICD 750800115
- [AD4] Herschel/Planck Instrument Interface document Part A
SCI-PT-IIDA-04624 Issue 3.3 Annex 10

3.2 Reference Documents

- [RD1] Planck FM TV/TB test specification
H-P-3-ASP-TS-0893
- [RD2] Planck LFI User Manual
PL-LFI-PST-MA-001
- [RD3] Planck LFI REBA Herschel PACS SPU: LFI REBA FMs User's Manual
PL-FPL-MA-1214-04 CRS
- [RD4] LFI- REBA application Software User Manual (SUM)
DS/UM_FIR/178v.4
- [RD5] LFI Short Functional test Procedure (SFT)
PL-LFI_PST-PR-018
- [RD6] Warm Functional test Procedure (WFT)
PL-LFI_PST-PR-017
- [RD7] Combined LFI EMC test at System level
PL-LFI_PST_PR_020
- [RD8] Planck FM TV test sequence
Issue 7.5 (Excel file)
- [RD9] Tuning of REBA scientific parameters
PL-LFI-PST-PR-024
- [RD10] IST1 and IST2 Combined LFI and HFI test
PL-LFI-PST-PR-019
- [RD11] TV tests: LFI Test Under Cryogenic Vacuum
PL-LFI-PST-PR-021



4 GENERAL REQUIREMENTS

4.1 Responsibilities

TAS-F will be the test conductor and will be the responsible of the test.
The Instrument Operation Team (IOT) will witness the tests and will support TAS-F during tests performing.

4.2 Environmental Conditions

All “Warm” operations outside CSL Chamber shall be conducted at ambient temperature, humidity, and pressure conditions in a class 100.000 environment or better in accordance with [AD2].
CSL Facility chamber as specification. [RD1]

4.3 Operational Constraints and Recommendations

LFI database loaded in CCS
I-EGSE Connected to CCS and fully tested.
TQL machine is connected to I-EGSE and fully tested.
TQL User Manual Available
LIFE machine available
LIFE User Manual Available.
IOT on site



5 Drain Currents Overlimits

With reference to the ACA tuning Verification test Ph 5-03-B-2 (Par. 5.6.5.3 [RD11]), there is a Warning, Warning 09, that states “The table of Cryo values must be checked by IOT before running the test. It might be the case that some biases values are different from FM and a new table should be produced.”

This will be the result of the check of the drain currents that is performed for the first time when the LFI is switch On at 20 K (see Ph 5-02-d) since one of the pass/fail criteria of this test is “Id currents are with margins expected” (as specified in the database). The check of the drain currents is in fact an important indicator of the status of the LFI instrument.

If one or several currents will not be within the limits, the procedure proposed here can give us an important indication of the status and health of the channels (ACAs not behaving as expected). The test will last approximately 3 hours.

Note that the implementation of this test will speed the process of investigation of the LFI behaviour in this new cold conditions, with the LFI integrated in the satellite.

To speed up the execution of the procedure the sequence is built to perform the test operating over two different ACAs in parallel. The chosen ACAs are belonging to different power groups and BEM trays, in order to minimize the coupling between radiometers biases. The sequence chosen for the channels is the same as for the matrix tuning, and is indicated in the table below.

RCA Under Tests in parallel
RCA 18 + RCA 21
RCA 19 + RCA 22
RCA 20 + RCA 23
RCA 25 + RCA 24
RCA 26 + RCA 27
RCA 28

	Name of Procedure	Reference	Note	Time
0	Start TQL session			
1	Update RCA parameters	Tab 35 Pag 42 [RD6] and new table to be produced when the contingency appears. See example in tab. 1	Apply the values 1 to N=9 of Vg1 and wait 20 second for each step on the first ACA of the FEMs Under Test	3 hours
2	Update RCA parameters	Tab 35 Pag 42 [RD6]	Apply the Vg1 Cryo values on the first ACA	



TV Tests: Contingency procedure due to drain currents overlimit

Document No.: PL-LFI-PST-PR-027
 Issue/Rev. No.: 1.0
 Date: June 10th 2008
 Page: 6

	Name of Procedure	Reference	Note	Time
		and Tab 45 pag 86 [RD11]	of the FEMs Under Test	
3			Repeat step 1 and 2 for all the other 3 ACAs of the FEMs under test	
4	Update RCA parameters	Tab 35 Pag 42 [RD6] and new table to be produced when the contingency appears. See example in tab. 1	Apply the values 1 to N=9 of Vg2 and wait 20 second for each step on the first ACA of the FEMs Under Test	
5	Update RCA parameters	Tab 35 Pag 42 [RD6] and Tab 45 pag 86 [RD11]	Apply the Vg2 Cryo values on the first ACA of the FEMs Under Test	
6			Repeat step 4 and 5 for all the other 3 ACAs of the FEMs under test	
7			Repeat step 1 to 6 for all the FEMs	
12	Stop TQL session and save data file			



TV Tests: Contingency procedure due to drain currents overlimit

Document No.: PL-LFI-PST-PR-027
 Issue/Rev. No.: 1.0
 Date: June 10th 2008
 Page: 7

RCA #	Detector ID		SCOS Paramet er	Start Values				Stop Values				Step Vg1	Step Vg2
				Vg1		Vg2		Vg1		Vg2			
				DEC	HEX	DEC	HEX	DEC	HEX	DEC	HEX	DEC	DEC
CH27	00	M1	LP001320										
	01	M2	LP002320										
	02	S1	LP003320										
	03	S2	LP004320										
CH24	04	M2	LP005320										
	05	M1	LP006320										
	06	S2	LP007320										
	07	S1	LP008320										
CH21	08	S2	LP009320										
	09	S1	LP010320										
	0A	M1	LP011320										
	0B	M2	LP012320										
CH22	0C	S2	LP013320										
	0D	S1	LP014320										
	0E	M1	LP015320										
	0F	M2	LP016320										
CH23	10	S2	LP017320										
	11	S1	LP018320										
	12	M1	LP019320										
	13	M2	LP020320										
CH25	14	M1	LP021320										
	15	M2	LP022320										
	16	S1	LP023320										
	17	S2	LP024320										
CH28	18	M1	LP025320										
	19	M2	LP026320										
	1A	S1	LP027320										
	1B	S2	LP028320										
CH20	1C	S2	LP029320										
	1D	S1	LP030320										
	1E	M1	LP031320										
	1F	M2	LP032320										
CH19	20	S2	LP033320										
	21	S1	LP034320										
	22	M1	LP035320										
	23	M2	LP036320										
CH18	24	S2	LP037320										
	25	S1	LP038320										
	26	M1	LP039320										
	27	M2	LP040320										
CH26	28	M2	LP041320										
	29	M1	LP042320										
	2A	S2	LP043320										
	2B	S1	LP044320										

1. Tab Example for the verification procedure