



Publication Year	2022
Acceptance in OA	2022-12-15T11:36:08Z
Title	Snapshot of a magnetohydrodynamic disk wind traced by water maser observations
Authors	MOSCADELLI, Luca, SANNA, ALBERTO, Beuther, Henrik, Oliva, André, Kuiper, Rolf
Publisher's version (DOI)	10.1038/s41550-022-01754-4
Handle	http://hdl.handle.net/20.500.12386/32748
Journal	NATURE ASTRONOMY
Volume	6

Snapshot of a magnetohydrodynamic disk wind traced by water maser observations

L. Moscadelli^{*1}, A. Sanna^{2,3}, H. Beuther⁴, G.A. Oliva^{5,6}, and R. Kuiper⁷

¹ INAF-Osservatorio Astrofisico di Arcetri, Largo E. Fermi 5, 50125 Firenze, Italy
e-mail: luca.moscadelli@inaf.it

² INAF-Osservatorio Astronomico di Cagliari, Via della Scienza 5, 09047, Selargius, CA, Italy

³ Max-Planck-Institut für Radioastronomie, Auf dem Hügel 69, D-53121 Bonn, Germany

⁴ Max Planck Institute for Astronomy, Königstuhl 17, D-69117 Heidelberg, Germany

⁵ Institut für Astronomie und Astrophysik, Universität Tübingen, Auf der Morgenstelle 10, D-72076 Tübingen, Germany

⁶ Space Research Center (CINESPA), School of Physics, University of Costa Rica, 11501 San José, Costa Rica

⁷ Faculty of Physics, University of Duisburg-Essen, Lotharstraße 1, D-47057 Duisburg, Germany

Key words. ISM: jets and outflows – ISM: kinematics and dynamics – Stars: formation
– Masers – Techniques: interferometric

The formation of astrophysical objects of different nature and size, from black holes to gaseous giant planets, involves a disk-jet system, where the disk drives the mass accretion onto a central compact object and the jet is a fast collimated ejection along the disk rotation axis. Magnetohydrodynamic disk winds can provide the link between mass accretion and ejection, which is essential to ensure that the excess angular momentum is removed from the system and accretion onto the central object can proceed. However, up to now, we have been lacking direct observational proof of disk winds. This work presents a direct view of the velocity field of a disk wind around a forming massive star. Achieving a very high spatial resolution of ≈ 0.05 au, our water maser observations trace the velocities of individual streamlines emerging from the disk orbiting the forming star. We find that, at low elevation above the disk midplane, the




Fig. 1. Previous NOEMA, JVL A and VLBA observations^{24,26} towards IRAS 21078+5211. (a) The gray-scale (from 10 to 35 mJy beam⁻¹) map reproduces the NOEMA 1.37 mm continuum emission. The colored dots represent the channel emission peaks of the CH₃CN $J_K = 12_K-11_K$ ($K = 3-6$) and HC₃N $J = 24-23$ lines, with colors denoting the channel V_{LSR} : blue for $[-13.6, -10]$ and red $[-2.5, 0.5]$ km s⁻¹. The green (70%, 80%, and 90% of 0.50 mJy beam⁻¹) and white (from 30% to 90%, in steps of 10% of 0.096 mJy beam⁻¹) contours show the JVL A-Array continuum at 1.3 cm and 5 cm, respectively. (b) Colored dots and arrows give absolute positions and proper motions of the 22 GHz water masers determined with multi-epoch (2010–2011) VLBA observations, with colors denoting the maser V_{LSR} . The black contours (from 10% to 90%, in steps of 10% of 0.50 mJy beam⁻¹) indicate the JVL A-Array continuum at 1.3 cm. The dashed rectangle delimits the field of view plotted in Fig. 2a.

flow co-rotates with its launch point in the disk, in agreement with magneto-centrifugal acceleration where the gas is flung away along the magnetic field line anchored to the disk. Beyond the co-rotation point, the flow rises spiraling around the disk rotation axis along a helical magnetic field. We have performed (resistive-radiative-gravito-) magnetohydrodynamic simulations of the formation of a massive star starting from the gravitational collapse of a rotating cloud core threaded by a magnetic field. A magneto-centrifugally launched jet develops around the forming massive star which has properties matching many features of the maser and thermal (continuum and line) observations of our target. Our results are, presently, the clearest evidence for a magnetohydrodynamic disk wind, and show that water masers and forming massive stars provide a suitable combination of tracer and environment to allow us studying the disk-wind physics.

Magnetohydrodynamic (MHD) disk winds have been proposed to be the engines of the powerful jets observed at varying length scales in many diverse sources, from young stellar objects³² (YSO) to black holes⁴. According to the classical model of an ideal MHD disk wind⁴, in the reference frame co-rotating with the launch point, the flow streams along the magnetic field line anchored to the accretion disk. An observer at rest sees magneto-centrifugal acceleration: the magnetic field keeps the flow in co-rotation with its launch point while its radial distance increases, till reaching the Alfvén point where the poloidal kinetic and magnetic energies are equal. Beyond the Alfvén point, the flow spirals outward

along the rotation axis with a stably increasing ratio of the streaming onto the rotational velocity, until it gets eventually collimated into a fast jet^{29,14}. So far, the best observational evidence for a MHD disk wind has been the finding of line of sight velocity gradients transversal to the jet axis, which are interpreted in terms of jet rotation and the imprint of the magneto-centrifugal acceleration^{3,9,17,1}. However, that is an indirect evidence and the derivation of key parameters, as the launch radius and the magnetic lever arm, can be seriously affected by systematic biases³⁹. On scales of ~ 100 au, a few studies based on Very Long Baseline Interferometry (VLBI) maser (the laser equivalent at microwave band) observations have revealed rotating disk-like^{19,21,37}, conical²² or cylindrical⁵ maser distributions at the jet root, but the streamlines of a disk wind have been never traced, up to now.

IRAS 21078+5211 is a star forming region of high bolometric luminosity, $5 \times 10^3 L_{\odot}$ ²⁴ at a distance of 1.63 ± 0.05 kpc⁴⁰, and harbors a YSO significantly more massive than the Sun. On scales of a few 100 au, by employing the NOthern Extended Millimeter Array (NOEMA), a disk²⁶ is observed in high-density molecular tracers (CH_3CN and HC_3N , see Fig. 1a) rotating around a YSO of mass of $5.6 \pm 2 M_{\odot}$. Interferometric observations at radio wavelengths (5 cm) using the Jansky Very Large Array (JVLA) have revealed a jet²⁴ directed NE-SW ($\text{PA} \approx 44^\circ$) emerging from the YSO, whose position at the center of the disk is pinpointed by compact thermal emission observed with the JVLA at 1.3 cm. During 2010–2011 we have performed multi-epoch Very Long Baseline Array (VLBA) observations of the maser emission of the water molecule at 22 GHz. These observations have discovered a cluster of masers placed ≈ 100 au NE from the YSO, whose proper motions are collimated NE-SW ($\text{PA} = 49^\circ$) and trace the base of the jet from the YSO²⁴ (see Fig. 1b). The analysis of the three-dimensional (3D) maser motions, specifically the local standard of rest (LSR) velocity (V_{LSR}) gradient transversal to the jet axis and the constant ratio between the toroidal and poloidal velocities, suggested that the jet could be launched from a MHD disk wind.

In October 2020, we performed novel observations (see Fig. 2a) of the water maser emission in IRAS 21078+5211 by including all telescopes available in the VLBI network, with the aim to simulate next-generation radio interferometers which will improve current sensitivities by more than an order of magnitude (see Appendix A). In the following, we will show that these new observations prove that the water masers trace magnetized streams of gas emerging from the YSO's disk (see Fig. 2b and Appendix H). The maser emission concentrates in three regions to NE, N, and SW, inside the three dotted rectangles of Fig. 2a. Along the jet axis (the dashed red line in Fig. 2a), whose sky-projection is known from previous observations of the maser proper motions and radio jet (see Appendix E), we observe two elongated structures, blue- and red-shifted (with respect to the systemic V_{LSR} of the YSO: $V_{\text{sys}} = -6.4 \text{ km s}^{-1}$) to NE and SW, respectively. These structures are

the opposite lobes of a collimated outflow from the YSO, located in between the two lobes; the disk axis (the black dashed line in Fig. 2a) is the intercept of the jet axis at the YSO position. From previous VLBA observations we know that the jet axis has to lay close to the plane of the sky, with an inclination $\leq 30^\circ$. According to the maser V_{LSR} , the jet is inclined towards us to NE, and away from us to SW.

The jet and disk axes provide a convenient coordinate system to refer the maser positions to. In the following, we present the interpretation of the maser kinematics, which is based on the analysis of the three independent observables: z , the elevation above the disk plane (or offset along the jet), R , the radial distance from the jet axis (or transversal offset), and the maser V_{LSR} . As discussed in Appendix A, the accuracy of the maser positions is ≈ 0.05 au, and that of the maser $V_{\text{LSR}} \approx 0.5 \text{ km s}^{-1}$. Without loss of generality, we can express the maser velocities as the sum of two terms, one associated with the toroidal component or rotation around the jet axis, V_{rot} , and the other associated with the poloidal component including all the contributions owing to non-rotation, V_{off} . Since the jet axis is close to the plane of the sky and we observe the rotation close to edge-on (see Fig 3), we can write:

$$V_{\text{LSR}} = V_{\text{off}} + V_{\text{rot}} = V_{\text{off}} + \omega \Re \sin(\phi) \quad (1)$$

$$R = \Re \sin(\phi) \quad (2)$$

$$\phi = \omega t \quad (3)$$

where ϕ is the angle between the rotation radius $\Re$ and the line of sight, and ω and t are the angular velocity and the time, respectively.

Fig. 4c shows the remarkable finding that the spatial coordinates z and R of the maser emission in the SW flow satisfy the relation:

$$R = C \sin(f_z(z - z_0)) \quad (4)$$

where C , the amplitude of the sinusoid, f_z , the spatial frequency, and z_0 , the position of zero phase, are fitted constants (see Table 1). In Appendix B we demonstrate that the masers in the NE flow can be separated in three different streams, each of them satisfying the relation 4 (see Fig. 5c and Table 1). The comparison of Eqs. 2 and 4 leads to a straightforward interpretation of the sinusoidal relation between the coordinates by taking: 1) $\Re = C$, and 2) $\phi = f_z |z - z_0|$. The former equation indicates that the rotation radius is the same for all the masers, the latter shows that the motions of rotation around and streaming along the jet axis are locked together, which is the condition for a spiral motion. Denoting with V_z the streaming velocity along the jet axis, we can write $|z - z_0| = V_z t$ and, comparing with Eq. 3, we derive the relation between the rotation and streaming

velocities:

$$f_z = \omega/V_z \quad (5)$$

According to Eq. 5, the observation of a well defined sinusoidal pattern requires that ω and V_z are directly proportional, or constant. The constancy of V_z implies that V_{off} is also constant, because, if the rotation radius does not change, V_{off} is the projection along the line of sight of V_z . Following Eqs. 1 and 2, the constancy of ω and V_{off} would result into a tight linear correlation between V_{LSR} and transversal offsets R . While a good linear correlation between V_{LSR} and R is observed for the SW and NE-1 spiral motions (see Figs. 4b and 5b, black symbols), the scatter in velocity is considerable for the NE-2 spiral motion (see Fig. 5b, red symbols). In Appendix D we investigate the physical reason for the observation of well defined sinusoidal patterns despite the presence of a significant velocity scatter. Applying the equations of motions for an axisymmetric MHD flow, we find that the magnetic field configuration has to be helical over the maser emission region, and the motion along such an helical field line, in the reference frame co-rotating with the launch point, leads to the sinusoidal pattern of maser positions.

We consider now the N region (see Fig. 2a) and show that, in this region as well, the maser kinematics is consistent with the predictions for a MHD disk wind. The N masers have a larger separation from the jet axis than the NE and SW masers. A few nearby masers show quite different V_{LSR} , which could hint at distinct streams, as observed (see Fig. 5a) and discussed (see Appendix B) for the NE flow. In this case, however, only a single stream is reasonably well sampled in position and V_{LSR} with the masers, and we focus our kinematical analysis on that. The spatial distribution of this stream presents an arc-like shape: a subset of maser features draws a line at small angle with the disk axis and another group extends at higher elevations about parallel to the jet axis (see Fig. 6a). Fig. 6c shows that the maser V_{LSR} increases linearly with R in the range $-95 \text{ au} \lesssim R \lesssim -70 \text{ au}$ up to an elevation $z \approx 60 \text{ au}$. The relatively large separation from the jet axis and radial extent, and the arc-like shape of the maser distribution lead us to think that the N emission is observed close to the plane of the sky. In this case, the maser V_{LSR} should mainly trace rotation, which is also expected to be the dominant velocity component at low elevations above the disk. Then, the good linear correlation between V_{LSR} and R indicates that the masers co-rotate at the same angular velocity, $\omega_N = 0.274 \pm 0.005 \text{ km s}^{-1} \text{ au}^{-1}$, up to $R \approx -95 \text{ au}$ and $z \approx 60 \text{ au}$. A simple interpretation is in terms of a magneto-centrifugally accelerated stream of gas emerging from a point of the disk. A disk in Keplerian rotation around an YSO of about $5.6 M_\odot$ attains an angular velocity equal to ω_N at $R \approx 40 \text{ au}$. The line drawn by the masers at the lowest elevations intercepts the disk axis close to -40 au (see Fig. 6a), as expected if the gas, launched from the disk, first streams approximately along a straight line and then progressively bends up along the jet axis. Note that, basing on

Eqs. 1 and 2, the derivation of ω_N does not depend on the maser geometry. Therefore, the finding that the masers lay along a line intercepting the disk at ≈ -40 au provides an "a posteriori" test of the assumption that the N emission is observed close to the plane of the sky.

The masers found at elevation $z > 60$ au appear to set aside of the arc-like distribution (see Fig. 6a) and their V_{LSR} are significantly more negative and do not follow the linear correlation with the radius (see Fig. 6c). A natural interpretation is that the location at $R \approx -95$ au and $z \approx 60$ au is the Alfvén point of the stream, and beyond that the gas is not any longer co-rotating. The lever arm of the stream is $\approx (95 \text{ au})/(40 \text{ au}) = 2.4$, in agreement with the values of 2–3 predicted by theory^{34,33}. The more negative V_{LSR} are explained if V_z (and the absolute value of V_{off}) increases with the elevation, as a consequence of the magneto-centrifugal launching. The linear correlation between V_{LSR} and z ($dV_{\text{LSR}}/dz = -0.195 \pm 0.002 \text{ km s}^{-1} \text{ au}^{-1}$) shown in Fig. 6b results from the combination of the two regimes: 1) sub-Alfvénic, where $V_{\text{LSR}} \propto R$ and the gas streams approximately along a straight line, that is $R \propto z$; 2) trans-Alfvénic, where V_z increases fast with z and V_{off} starts to be significant.

From the previous analysis, a MHD disk wind seems to be a natural frame to explain both the spiral motions traced by the masers close to the jet axis in the NE and SW regions and the gas co-rotation along the N stream. If some locations of the YSO's disk are perturbed, the flow emerging from those perturbed launch points should harbor internal shocks (see Appendix E), which travel outward along spiraling trajectories. These internal shocks provide physical conditions suitable for the excitation of the water masers^{8,10,12}. The spiral motions traced with the masers would correspond to portions of the trajectories beyond the Alfvén point where the rotation radius keeps about constant. An essential feature of the proposed model is that, as the launch point rotates, the maser emissions have to travel along spatially distinct, spiraling trajectories. These trajectories are invariant under rotation and nearby masers share the same orbital parameters. However, since the masers sample different trajectories, we need to make a distinction between the angular velocity of the trajectory, ω , derived through the linear fit of the maser V_{LSR} versus R (see Eqs. 1 and 2, and Figs. 4b and 5b), and the effective angular velocity of rotation, ω_e , the one to be used in Eqs. 3 and 5. Since the different trajectories are rigidly anchored to the launch point and water masers at higher (absolute) elevations have been launched earlier in time, the simple relation holds:

$$\omega_e = \omega - \omega_K \quad (6)$$

where ω_K is the Keplerian angular velocity of the launch point. Eq. 6 shows that ω_e is the angular velocity of the spiraling trajectory as observed in the reference frame co-rotating with the launch point. Based on axisymmetric MHD models^{31,39}, the ratio ω_K/ω

increases stably from 1 up to a value ≈ 4 while the gas climbs from z_A to $10 \mathfrak{R}_K$, where z_A is the elevation of the Alfvén point and $\mathfrak{R}_K$ is the launch radius. Being $\omega \leq \omega_K$, the negative value of ω_e indicates that the rotation angle of the maser positions decreases with z . Following the previous discussion, Eq. 5 has to be corrected by replacing ω with ω_e :

$$f_z = |\omega_e|/V_z \quad (7)$$

A good test of the above considerations comes directly from our data. Assuming that all the masers move along a single trajectory and using the fitted values of ω and f_z in Eq. 5, we obtain implausibly small values for V_z : 31, 37, 17 and 49 km s⁻¹, for the SW, NE-1, NE-2, and NE-3 spiral motions, respectively. There are two strong observational evidences that the derived streaming velocities are too small. First, comparing them with the values of V_{off} (see Table 1), the two velocities have similar amplitudes, and that is inconsistent with the expectation that V_{off} be the line of sight component of V_z and the jet axis being close to the plane of the sky. Second, taking the ratio between the highest elevations reached by the masers, that is 100–130 au (see Figs. 4 and 5), and the above values of V_z , the derived traveling times of 15–40 yr exceed the separation of 10 yr since the previous VLBA observations, when no maser emission was detected at corresponding positions.

Since V_{off} corresponds to the line of sight projection of V_z , we can write:

$$V_z = |V_{\text{off}} - V_{\text{sys}}| / \sin(i_{\text{axi}}) \quad (8)$$

where V_{off} is corrected for the systemic V_{LSR} of the YSO, and i_{axi} is the inclination angle of the jet axis with the plane of the sky. As we know that $i_{\text{axi}} \leq 30^\circ$, Eq. 8 allows us to derive a lower limit for V_z , reported in Table 2. Using the derived lower limit of V_z and the corresponding value of f_z (see Table 1), by means of Eq. 7 we can calculate a lower limit for ω_e . Finally, we use Eq. 6 and the fitted value of ω (see Table 1) to infer a lower limit for $\omega_K = \omega + |\omega_e|$ and, knowing the mass of the YSO, a corresponding upper limit for the launch radius $\mathfrak{R}_K$ (see Table 2). The NE-1 stream, which extends the most in elevation (from 20 to 130 au, see Fig. 5a), includes a group of maser features at elevation of ≈ 20 au, which should be located closer to the Alfvén point. In Appendix F, we study the change of V_{LSR} versus R internal to this cluster and obtain a lower limit for $\omega_K \geq 2.4$ km s⁻¹ au⁻¹ that agrees well with the corresponding value reported in Table 2 for the NE-1 stream. The results shown in Table 2 are in general agreement with the theoretical predictions from MHD disk winds^{34,33}: the inferred lower limits on the streaming velocity V_z increase steeply with decreasing launch radius; for the SW and NE-3 streams, which are those with

relatively lower uncertainty in the measurement of both ω and $\mathfrak{R}$ (see Table 1), the ratio between V_z and the rotation velocity $\omega \mathfrak{R}$ is ≥ 2 –3.

In conclusion, our observations resolve, for the first time, the kinematics of a MHD disk wind on length scales of 1–100 au, allowing us to study the velocity pattern of individual streamlines launched from the disk. As represented in Fig. 2b, close to the disk rotation axis we observe flows spiraling outward along a helical magnetic field, launched from locations of the disk at radii ≤ 6 –17 au. At larger separation from the rotation axis, we observe a stream of gas co-rotating with its launch point from the disk at radius of ≈ 40 au, in agreement with the predictions for magneto-centrifugal acceleration. Our interpretation is supported by (resistive-radiative-gravito-) MHD simulations of the formation of a massive star that lead to a magneto-centrifugally launched jet whose properties agree with our maser and thermal (continuum and line) observations of IRAS 21078+5211. These results provide the best evidence for a MHD disk wind to date. Since water maser emission is widespread in YSOs, sensitive VLBI observations of water masers can be a valuable tool to investigate the physics of disk winds.

Acknowledgments

We thank Christian Fendt and Daniele Galli for very useful discussion. GAO acknowledges financial support from the Deutscher Akademischer Austauschdienst (DAAD), under the program Research Grants - Doctoral Projects in Germany, and complementary financial support for the completion of the Doctoral degree by the University of Costa Rica, as part of their scholarship program for postgraduate studies in foreign institutions. HB acknowledges support from the European Research Council under the Horizon 2020 Framework Programme via the ERC Consolidator Grant CSF-648505. HB also acknowledges support from the Deutsche Forschungsgemeinschaft in the Collaborative Research Center (SFB 881) “The Milky Way System” (subproject B1). RK acknowledges financial support via the Emmy Noether and Heisenberg Research Grants funded by the German Research Foundation (DFG) under grant no. KU 2849/3 and 2849/9. The European VLBI Network is a joint facility of independent European, African, Asian, and North American radio astronomy institutes. Scientific results from data presented in this publication are derived from the following EVN project code: GM077.

References

- [1] S. Aalto, N. Falstad, S. Muller, and others. ALMA resolves the remarkable molecular jet and rotating wind in the extremely radio-quiet galaxy NGC 1377. *A&A*, 640:A104, Aug. 2020. .
- [2] G. Anglada, L. F. Rodríguez, and C. Carrasco-González. Radio jets from young stellar objects. *A&A Rev.*, 26(1):3, Jun 2018. .

- [3] F. Bacciotti, T. P. Ray, R. Mundt, and others. Hubble Space Telescope/STIS Spectroscopy of the Optical Outflow from DG Tauri: Indications for Rotation in the Initial Jet Channel. *ApJ*, 576(1):222–231, Sep 2002. .
- [4] R. D. Blandford and D. G. Payne. Hydromagnetic flows from accretion disks and the production of radio jets. *MNRAS*, 199:883–903, June 1982. .
- [5] R. A. Burns, H. Imai, T. Handa, and others. A ‘water spout’ maser jet in S235AB-MIR. *MNRAS*, 453(3):3163–3173, Nov. 2015. .
- [6] A. Caratti o Garatti, B. Stecklum, R. Garcia Lopez, and others. Disk-mediated accretion burst in a high-mass young stellar object. *Nature Physics*, 13:276–279, Mar. 2017. .
- [7] M. Elitzur, D. J. Hollenbach, and C. F. McKee. H₂O masers in star-forming regions. *ApJ*, 346:983–990, Nov. 1989.
- [8] M. Elitzur, D. J. Hollenbach, and C. F. McKee. Planar H₂O masers in star-forming regions. *ApJ*, 394:221–227, July 1992. .
- [9] T. Hirota, M. N. Machida, Y. Matsushita, and others. Disk-driven rotating bipolar outflow in Orion Source I. *Nature Astronomy*, 1:0146, July 2017. .
- [10] D. Hollenbach, M. Elitzur, and C. F. McKee. Interstellar H₂O Masers from J Shocks. *ApJ*, 773:70, Aug. 2013. .
- [11] T. R. Hunter, C. L. Brogan, G. MacLeod, and others. An Extraordinary Outburst in the Massive Protostellar System NGC6334I-MM1: Quadrupling of the Millimeter Continuum. *ApJ*, 837(2):L29, Mar. 2017. .
- [12] M. J. Kaufman and D. A. Neufeld. Water Maser Emission from Magnetohydrodynamic Shock Waves. *ApJ*, 456:250–+, Jan. 1996.
- [13] A. Kölligan and R. Kuiper. Jets and outflows of massive protostars. From cloud collapse to jet launching and cloud dispersal. *A&A*, 620:A182, Dec 2018. .
- [14] R. Krasnopolsky, Z.-Y. Li, and R. Blandford. Magnetocentrifugal Launching of Jets from Accretion Disks. I. Cold Axisymmetric Flows. *ApJ*, 526(2):631–642, Dec. 1999. .
- [15] R. Kuiper, H. Klahr, H. Beuther, and T. Henning. Circumventing the Radiation Pressure Barrier in the Formation of Massive Stars via Disk Accretion. *ApJ*, 722:1556–1576, Oct. 2010. .
- [16] R. Kuiper, H. W. Yorke, and A. Mignone. Makemake + Sedna: A Continuum Radiation Transport and Photoionization Framework for Astrophysical Newtonian Fluid Dynamics. *ApJS*, 250(1):13, Sept. 2020. .
- [17] C.-F. Lee, P. T. P. Ho, Z.-Y. Li, and others. A rotating protostellar jet launched from the innermost disk of HH 212. *Nature Astronomy*, 1:0152, July 2017. .
- [18] M. N. Machida, S.-i. Inutsuka, and T. Matsumoto. Magnetic Fields and Rotations of Protostars. *ApJ*, 670(2):1198–1213, Dec. 2007. .
- [19] L. D. Matthews, L. J. Greenhill, C. Goddi, and others. A Feature Movie of SiO Emission 20-100 AU from the Massive Young Stellar Object Orion Source I. *ApJ*, 708:80–92, Jan. 2010. .

- [20] A. Mignone, G. Bodo, S. Massaglia, and others. PLUTO: A Numerical Code for Computational Astrophysics. *ApJS*, 170(1):228–242, May 2007. .
- [21] L. Moscadelli and C. Goddi. A multiple system of high-mass YSOs surrounded by disks in NGC 7538 IRS1 . Gas dynamics on scales of 10-700 AU from CH₃OH maser and NH₃ thermal lines. *A&A*, 566:A150, June 2014. .
- [22] L. Moscadelli, R. Cesaroni, M. J. Rioja, and others. Methanol and water masers in IRAS 20126+4104: the distance, the disk, and the jet. *A&A*, 526:A66+, Feb. 2011. .
- [23] L. Moscadelli, A. Sanna, and C. Goddi. Unveiling the gas kinematics at 10 AU scales in high-mass star-forming regions. Milliarcsecond structure of 6.7 GHz methanol masers. *A&A*, 536:A38, Dec. 2011. .
- [24] L. Moscadelli, Á. Sánchez-Monge, C. Goddi, and others. Outflow structure within 1000 au of high-mass YSOs. I. First results from a combined study of maser and radio continuum emission. *A&A*, 585:A71, Jan. 2016. .
- [25] L. Moscadelli, A. Sanna, C. Goddi, and others. Protostellar Outflows at the Earliest Stages (POETS). IV. Statistical properties of the 22 GHz H₂O masers. *A&A*, 635:A118, Mar. 2020. .
- [26] L. Moscadelli, H. Beuther, A. Ahmadi, and others. Multi-scale view of star formation in IRAS 21078+5211: from clump fragmentation to disk wind. *A&A*, 647:A114, Mar. 2021. .
- [27] T. C. Mouschovias and J. Spitzer, L. Note on the collapse of magnetic interstellar clouds. *ApJ*, 210:326, Dec. 1976. .
- [28] G. A. Oliva and R. Kuiper. Modeling disk fragmentation and multiplicity in massive star formation. *A&A*, 644:A41, Dec. 2020. .
- [29] R. Ouyed and R. E. Pudritz. Numerical Simulations of Astrophysical Jets from Keplerian Disks. I. Stationary Models. *ApJ*, 482(2):712–732, June 1997. .
- [30] G. Pelletier and R. E. Pudritz. Hydromagnetic Disk Winds in Young Stellar Objects and Active Galactic Nuclei. *ApJ*, 394:117, July 1992. .
- [31] N. Pesenti, C. Dougados, S. Cabrit, and others. Predicted rotation signatures in MHD disc winds and comparison to DG Tau observations. *A&A*, 416:L9–L12, Mar. 2004. .
- [32] R. E. Pudritz and C. A. Norman. Centrifugally driven winds from contracting molecular disks. *ApJ*, 274:677–697, Nov. 1983. .
- [33] R. E. Pudritz and T. P. Ray. The Role of Magnetic Fields in Protostellar Outflows and Star Formation. *Frontiers in Astronomy and Space Sciences*, 6:54, July 2019. .
- [34] R. E. Pudritz, R. Ouyed, C. Fendt, and A. Brandenburg. Disk Winds, Jets, and Outflows: Theoretical and Computational Foundations. In B. Reipurth, D. Jewitt, and K. Keil, editors, *Protostars and Planets V*, page 277, Jan 2007.
- [35] M. J. Reid, M. H. Schneps, J. M. Moran, and others. The distance to the center of the galaxy - h₂o maser proper motions in sagittarius b2(n). *ApJ*, 330:809, 1988.

- [36] A. Sanna, L. Moscadelli, R. Cesaroni, and others. VLBI study of maser kinematics in high-mass star-forming regions. I. G16.59-0.05. *A&A*, 517:A71+, July 2010. .
- [37] A. Sanna, G. Surcis, L. Moscadelli, and others. Velocity and magnetic fields within 1000 AU of a massive YSO. *A&A*, 583:L3, Nov. 2015. .
- [38] J. Staff, N. Koning, R. Ouyed, and R. Pudritz. Three-dimensional simulations of MHD disk winds to hundred AU scale from the protostar. In *European Physical Journal Web of Conferences*, volume 64 of *European Physical Journal Web of Conferences*, page 05006, Jan. 2014. .
- [39] B. Tabone, S. Cabrit, G. Pineau des Forêts, and others. Constraining MHD disk winds with ALMA. Apparent rotation signatures and application to HH212. *A&A*, 640:A82, Aug. 2020. .
- [40] Y. Xu, J. J. Li, M. J. Reid, and others. On the Nature of the Local Spiral Arm of the Milky Way. *ApJ*, 769:15, May 2013. .
- [41] Q. Zhang, B. Claus, L. Watson, and J. Moran. Angular Momentum in Disk Wind Revealed in the Young Star MWC 349A. *ApJ*, 837(1):53, Mar. 2017. .

Table 1. Parameters of the linear and sinusoidal fits

Stream	Linear fit		Sinusoidal fit		
	ω (km s ⁻¹ au ⁻¹)	V_{off} (km s ⁻¹)	$\Re$ (au)	f_z (rad au ⁻¹)	z_0 (au)
SW	1.15 ± 0.12	17.5 ± 1.3	21.6 ± 1.0	0.0366 ± 0.0012	-16.5 ± 1.9
NE-1	1.15 ± 0.09	-29.2 ± 0.6	36 ± 5	0.0307 ± 0.0008	16.3 ± 2.0
NE-2	0.64 ± 0.27	-10.9 ± 3.0	22.9 ± 0.5	0.0386 ± 0.0008	47.8 ± 1.2
NE-3	2.0 ± 0.5^a	-49 ± 27	17.2 ± 0.3	0.0405 ± 0.0023	7.3 ± 2.3

Notes.

Column 1 denotes the maser stream; Cols. 2 and 3 provide the values of ω and V_{off} from the linear fit of maser V_{LSR} versus R ; Cols. 4, 5 and 6 report the amplitude, the spatial frequency and the position of zero phase, respectively, of the sinusoidal fit of the maser coordinates R versus z .

^a The determination of this error, smaller than the value, $1.7 \text{ km s}^{-1} \text{ au}^{-1}$, from the linear fit, is discussed in Appendix C.




Fig. 2. October 2020, global VLBI observations of the 22 GHz water masers and 3D view of the proposed interpretation for the maser kinematics. (a) Colored dots give absolute positions of the 22 GHz water masers, with colors denoting the maser V_{LSR} . The black dotted rectangles encompass the three regions, to the N, NE and SW, where maser emission concentrate. The blue dashed rectangle delimits the area of maser emission in the previous VLBA observations, and three distinct maser clusters S of the YSO are labeled “C1”, “C2”, and “C3” (see Appendix G). The red and black dashed lines mark the sky-projected jet and disk axis, respectively. (b) Observed maser positions (red and orange dots) overlaid on top of streamlines (blue lines) computed from resistive-radiative-gravito-MHD simulations of a jet around a forming massive star (see Appendix H). The streamlines close to the rotation axis show significant spiraling motion, in agreement with the kinematic signature of the masers observed in the NE and SW regions. The wide streamline from the simulation illustrates the outflowing trajectory of material from the outer disk, similar to the observed masers in the N region. For context, the protostar, the disk and the outflow cavity have been sketched in gray, based on the density structure obtained in the simulations (see Fig. H.1).

Table 2. Estimate of the stream parameters

Stream	V_z (km s ⁻¹)	ω_K (km s ⁻¹ au ⁻¹)	$\mathfrak{R}_K$ (au)
SW	≥ 48	≥ 2.9	≤ 9
NE-1	≥ 46	≥ 2.6	≤ 10
NE-2	≥ 9	≥ 1.0	≤ 17
NE-3	≥ 85	≥ 5.4	≤ 6

Notes.

Column 1 indicates the maser stream; Col. 2 reports the estimated streaming velocity along the jet axis; Cols. 3 and 4 give the estimate of the angular velocity and the radius, respectively, at the launch point.




Fig. 3. Illustration of the spiral motion of the masers (small red balls) along a magnetic field line (blue) emerging from the YSO's disk. The rotation angle, ϕ , and radius, $\mathfrak{R}$, are labeled. The field line is anchored to a point of the disk rotating at an angular velocity ω_K . This plot is based on the data from (resistive-radiative-gravito-) MHD simulations of a jet around a forming massive star (see Appendix H).




Fig. 4. The SW spiral motion. (a) Expanding view of the maser positions and V_{LSR} in the SW region. Colored dots have the same meaning as in Fig. 2a. The distances along the jet (red) and disk (black) axes are indicated. (b) Plot of the maser V_{LSR} (and corresponding errors, denoted with errorbars) versus R . The black dashed and dotted lines show the best linear fit and the associated uncertainty, respectively. (c) Plot of the maser coordinates R versus z . The positional error is smaller than the cross size. The black dashed curve is the fitted sinusoid, whose parameters are reported in Table 1.




Fig. 5. The NE spiral motions. (a) Expanding view of the maser positions and V_{LSR} in the NE region. Different symbols are employed to identify the three spiral motions: dots for the NE-1, triangles for the NE-2, and squares for the NE-3 spiral motion. Colors denote the maser V_{LSR} . The distances along the jet (red) and disk (black) axes are indicated. The black dashed rectangle encompasses the maser cluster closest to the YSO. (b) In this and following panel, black, red, and blue colors refer to masers belonging to the NE-1, NE-2, and NE-3 streams, respectively. Errorbars, dashed and dotted lines have the same meaning as in Fig. 4b. Masers in the NE-2 stream with similar radii, $10 \text{ au} \leq R \leq 22 \text{ au}$, but different elevations, $60 \text{ au} \leq z < 90 \text{ au}$ and $z \geq 90 \text{ au}$, have V_{LSR} different by $\approx 10 \text{ km s}^{-1}$ (see Appendix D). For the NE-2 stream, the linear fit of the V_{LSR} has been performed considering only the masers with $z \geq 90 \text{ au}$. (c) Plot of the linear transformation of R versus z . For each of the three streams, the coefficients A and B are taken equal to the corresponding values of ω and V_{off} , respectively, in Table 1. We plot the linear transformation of the radii to reduce the overlap and improve the visibility of each of the three streams. The dashed curves are the fitted sinusoids. In Table 1, we report the parameters of the sinusoidal fits of the radii.




Fig. 6. The co-rotating N stream. (a) Expanding view of the maser positions and V_{LSR} in the N region. Colored dots and triangles give absolute positions of the 22 GHz water masers, with colors denoting the maser V_{LSR} . The triangles mark a few masers with detached V_{LSR} excluded from the kinematical analysis. The distances along the jet (red) and disk (black) axes are indicated. The black dashed line shows the linear fit of the positions of the masers at elevation $z < 20$ au. Plot of maser V_{LSR} versus z (b) and R (c). In both panels, errorbars give the maser V_{LSR} and corresponding errors, and the black dashed and dotted lines show the best linear fit and the associated uncertainty, respectively. The linear fit of V_{LSR} versus R has been performed considering only the masers with $V_{\text{LSR}} \geq -27 \text{ km s}^{-1}$.

Appendix A: Observations

We observed the $6_{16} - 5_{23}$ H_2O maser transition (rest frequency 22.235079 GHz) towards IRAS 21078+5211 (tracking center: $\text{RA}(\text{J2000}) = 21^{\text{h}}9^{\text{m}}21^{\text{s}}.720$ and $\text{Dec}(\text{J2000}) = +52^{\circ}22'37''.08$) with global VLBI for 24 hr, starting on 2020 October 27, 13:30 UT. The antennae involved were 16 antennae of the European VLBI network (EVN): Yebes, Sardinia, Medicina, Jodrell_Bank, Effelsberg, Onsala, Metsahovi, Torun, Svetloe, Badary, Zelenchukskaya, KVN_Tamna, KVN_Ulsan, KVN_Yonsei, Urumqi, Tianma; plus the 10 antennae of the VLBA: Brewster, Fort Davis, Hancock, Kitt Peak, Los Alamos, Mauna Kea, North Liberty, Owens Valley, Pie Town, and Saint Croix. The observations were designed to achieve a relative and absolute position accuracy of ~ 0.01 mas and ~ 1 mas, respectively, and to reach a sensitivity in the maser line ≤ 1 mJy beam $^{-1}$. While the EVN antennae observed continuously the target, interleaving calibration scans ≈ 8 min long every hour, the VLBA performed also phase-referencing observations (over 10 hr), alternating scans on the target and the phase-reference calibrator every 45 s. During the phase-reference session, the target and the calibrators were always observed by the VLBA simultaneously with the EVN to ensure global VLBI baselines. The fringe-finder and bandpass calibrators were: J2202+4216, 2007+777, 3C84 and 3C48; the phase-reference calibrators were 2116+543 and 2051+528, both within 2.5° from the target and with a correlated flux of ~ 0.1 Jy beam $^{-1}$ at 22 GHz.

We recorded dual circular polarization through four adjacent bandwidths of 16 MHz, one of them centered at the maser V_{LSR} of -6.4 km s $^{-1}$. The four 16 MHz bandwidths were used to increase the signal to noise ratio (SNR) of the weak continuum (phase-reference) calibrators. The data were correlated with the SFXC correlator at the Joint Institute for VLBI in Europe (JIVE, at Dwingeloo, the Netherlands) in two correlation passes, using 1024 and 128 spectral channels to correlate the maser 16 MHz bandwidth and the whole set of four 16 MHz bandwidths, respectively. The spectral resolution attained across the maser 16 MHz band was 0.21 km s $^{-1}$. The correlator averaging time was 1 s.

Data were reduced with the Astronomical Image Processing System (AIPS) package following the VLBI spectral line procedures³⁶. The emission of an intense and compact maser channel was self-calibrated, and the derived (amplitude & phase) corrections were applied to all the maser channels before imaging. To cover the whole maser emission, we produced images extending $0''.65$ in both $\text{RA} \cos \delta$ and DEC , and 84 km s $^{-1}$ in V_{LSR} . Using natural weighting, the FWHM major and minor sizes of the beam are 0.7 mas and 0.3 mas, respectively, and the beam PA is -49° . In channel maps with (relatively) weak signal, the 1σ rms noise is 0.7 mJy beam $^{-1}$, close to the expected thermal noise.

Inverse phase-referencing³⁶ produced good SNR (≥ 10) images of the two phase-reference calibrators. Taking into account that the calibrators are relatively compact with size

$\lesssim 1$ mas, and that the absolute position of the calibrators is known within a few 0.1 mas, we estimate that the error on the absolute position of the masers is $\lesssim 0.5$ mas.

Table A.3 reports the parameters (intensity, V_{LSR} , position) of the 22 GHz water masers in IRAS 21078+5211. Individual maser features are a collection of quasi-compact spots observed on contiguous channel maps and spatially overlapping (within their FWHM size). The spot positions are determined by fitting a two-dimensional elliptical Gaussian to their spatial emissions. The uncertainty of the spot position relative to the reference maser channel is the contribution of two terms: $\Delta\theta_{\text{spot}} = \sqrt{\Delta\theta_{\text{fit}}^2 + \Delta\theta_{\text{bandpass}}^2}$. The first term depends on the SNR of the data, following³⁵: $\Delta\theta_{\text{fit}} = \theta_{\text{beam}} / (2 \text{ SNR})$, where θ_{beam} is the resolution beam size, conservatively taken equal to the FWHM major beam size of 0.7 mas. The second term depends on the accuracy of the bandpass calibration through the expression⁴¹: $\Delta\theta_{\text{bandpass}} = \theta_{\text{beam}} (\Delta\Psi/360^\circ)$, where $\Delta\Psi$ in degrees is the phase stability across the observing band. In our case $\Delta\Psi \lesssim 10^\circ$ and $\Delta\theta_{\text{bandpass}} \lesssim 0.02$ mas becomes the dominant error term for spot intensity ≥ 100 mJy beam⁻¹. The maser feature position (and corresponding error) is estimated from the error-weighted mean of the spot positions (and corresponding errors), and the feature V_{LSR} from the intensity-weighted mean of the spots' V_{LSR} . To be conservative, the uncertainty on the feature V_{LSR} is taken equal to 0.5 km s⁻¹, corresponding to the typical maser FWHM line width.

Appendix B: Resolving the NE emission into three distinct streams

The masers in the NE emission are separated into three distinct streams identified with different symbols: dots, triangles and squares (see Fig. 5a). Each stream traces a sinusoid in the plane of the sky (see Fig. 5c), which is the signature for a spiral motion. The identification of the maser features belonging to each of the three sinusoids can be done with good confidence. First, we note that the masers at elevation $z \geq 90$ au can be unambiguously divided into two streams, dots and triangles, on the basis of the very different V_{LSR} of nearby emissions. Both dots and triangles at $z \geq 90$ au have R decreasing with z , suggesting that they could trace the descending portion of a sinusoid, and one can argue that the corresponding ascending portion would be traced by masers with $z < 90$ au. Next, we note that the group of masers with $30 \text{ au} \leq z \leq 60 \text{ au}$ draw an arc, and, since they cannot be part of a sinusoid together with other masers at larger R , they have to trace a third sinusoid with maximum radius close to the radius, $R_{\text{apex}} = 17.2$ au, of the apex of the arc. We have also verified that the blue-shifted cluster of masers located at elevation $z \approx 20$ au (inside the dashed rectangle of Fig. 5a) cannot be adjusted within this third sinusoid. We have fitted the expression:

$$R = (R_{\text{apex}} - C) + C \sin(f_z(z - z_0)) \quad (\text{B.1})$$




Fig. B.1. Integrated emission map of the NE maser stream (see Fig. 5a). Emission summed over the whole velocity range $[-19, +1] \text{ km s}^{-1}$ by selecting groups of channels (top right) with similar noise thresholds. Colored contours correspond to a given velocity interval and increase at steps of 5 times the noise thresholds of each group (corresponding to $\approx 10\sigma$). Angular offsets correspond to Table A.3 and the linear scale is drawn in the top axis. The dashed red line denotes the jet axis and the synthesized VLBI beam is plotted in the bottom left corner.

with the maximum radius fixed to R_{apex} and the zero level given by $R_{\text{apex}} - C$, with C free parameter. When the masers at elevation $z \approx 20 \text{ au}$ and those drawing the arc at $30 \text{ au} \leq z \leq 60 \text{ au}$ are considered together, the fit of Eq. B.1 results into an implausible, very negative zero level at $\approx -60 \text{ au}$. Thus, after putting all the masers with $30 \text{ au} \leq z \leq 60 \text{ au}$ (and only them) into a third spiral motion, it remains to deal only with the masers in the two separated ranges $20 \text{ au} \leq z < 30 \text{ au}$ and $60 \text{ au} \leq z < 90 \text{ au}$. The sinusoidal fit of R versus z of the triangles at $z \geq 90 \text{ au}$ indicates that the ascending portion of the sinusoid has to extend from $\approx 50 \text{ au}$ to $\approx 90 \text{ au}$, and, over that range of elevations, intercepts all the observed masers. Finally, the remaining masers at $20 \text{ au} \leq z < 30 \text{ au}$ trace the ascending portion of the sinusoid identified with dots in Fig. 5a.

Figure B.1 evidences the filamentary morphology of the maser emission in the NE region. First, we selected six velocity ranges (see Fig. B.1) of channel maps with similar noise thresholds. Then, we summed the emission of each group of channels, blanking pixels with emission below a typical threshold of $\approx 10\sigma$, and overplotted the six maps together. This method allows to appreciate the overall spatial structure traced by maser emission with very different brightness levels.




Fig. C.1. Constraining ω for the NE-3 stream. Plot of the rotation radius estimated from the ratio $\mathfrak{C}/\omega$ versus ω , where $\mathfrak{C}$ is the amplitude of the sinusoidal fit of the rotational velocity, ωR , versus z (see Appendix C). The blue continuous and dashed lines mark the observed value of the rotation radius and the corresponding range of uncertainty, respectively; the red dashed lines delimit the range of ω for which the fitted radius is consistent with the observations.

Appendix C: The angular velocity of the NE-3 stream

The NE-3 stream is sampled by the masers only close to the positions where it attains the maximum radius. Because of the small radial range, $15 \text{ au} \lesssim R \lesssim 17 \text{ au}$, the linear fit of V_{LSR} versus R constrains very little the angular velocity, $\omega = 2.04 \pm 1.72 \text{ km s}^{-1} \text{ au}^{-1}$. However, since R , and the rotational velocity ωR , are sinusoidal functions of the elevation z , we can use the results of the sinusoidal fits to reduce the error in ω . For plausible values of ω in the range 0–4, we have performed the sinusoidal fit of the rotational velocity, and estimated the radius from the ratio of the fitted amplitude, $\mathfrak{C}$, and ω . For a given value of ω , we have fitted the expression:

$$\omega R = (\omega R_{\text{apex}} - \mathfrak{C}) + \mathfrak{C} \sin(f_z(z - z_0)) \quad (\text{C.1})$$

fixing the maximum velocity to ωR_{apex} and fitting the zero level $\omega R_{\text{apex}} - \mathfrak{C}$, with the amplitude $\mathfrak{C}$ as a free parameter. Fig. C.1 shows that, apart a minor fraction of scattered results, the radius estimated from the sinusoidal fit decreases regularly with ω , and attains a value consistent with the observations, $17.5 \pm 2.5 \text{ au}$, for $\omega = 2.0 \pm 0.5 \text{ km s}^{-1} \text{ au}^{-1}$, thus effectively reducing the uncertainty to $0.5 \text{ km s}^{-1} \text{ au}^{-1}$.

Appendix D: Velocity scatter

Figs. 4b and 5b show that the maser V_{LSR} are linearly correlated with R in the SW and NE-1 streams. For the masers belonging to the NE-2 stream, the measurement scatter from the linear fit of V_{LSR} versus R is considerable (with large fit errors, see Table 1), while, in the case of the NE-3 stream, the range in R is too small (2 au only) to constrain the parameters of the linear fit. The noticeable deviation of V_{LSR} from the linear fits seems difficult to conciliate with the accuracy with which the maser positions reproduce the sinusoidal patterns (see Figs. 4c and 5c). The average scatters of maser V_{LSR} and positions (along the jet axis from the fitted sinusoid) are 2.4 km s⁻¹ and 1.9 au, 3.1 km s⁻¹ and 3.8 au, 6.9 km s⁻¹ and 2.1 au, and 2.7 km s⁻¹ and 1.7 au, for the SW, NE-1, NE-2 and NE-3 streams, respectively. Assuming that the V_{LSR} scatter reflects mainly the variation of the streaming velocity V_z , since the jet axis is within 30° from the plane of the sky, the change in V_z has to be at least twice that observed in V_{LSR} . Then, using the above values, the ratios of the corresponding scatters in position and V_z give upper limits for the maser traveling times of ≤ 1 –3 yr. These traveling times, for maximum (absolute) elevations of the maser streams of 100–130 au (see Figs. 4 and 5), imply $V_z \geq 200$ –500 km s⁻¹, which appears to be too large with respect to the observed maser V_{LSR} . In the following, we investigate the physical reason for the observation of well defined sinusoidal patterns despite the co-occurrence of significant velocity scatters.

In a stationary, axisymmetric MHD flow, the two fundamental equations of motions^{30,34,33} linking velocity and magnetic field along a field line are:

$$\rho V_p = k B_p \quad (\text{D.1})$$

$$B_\phi = \frac{\rho}{k} (V_\phi - \omega_K \mathfrak{R}) \quad (\text{D.2})$$

where V_p and V_ϕ , and B_p and B_ϕ are the poloidal and toroidal components of the velocity and magnetic field, respectively, ρ is the gas mass volume density, ω_K is the Keplerian angular velocity at the launch point, $\mathfrak{R}$ is the rotation radius, and k is the "mass load" of the wind, expressing the fixed ratio of mass and magnetic fluxes along a given magnetic field line. Since $V_\phi - \omega_K \mathfrak{R}$ is the toroidal velocity in the reference frame co-rotating with the launch point, Eqs. D.1 and D.2 lead to the well-known result that the velocity and magnetic field vectors are always parallel in the co-rotating reference frame. Writing $V_\phi = \omega \mathfrak{R}$, where ω is the angular velocity of the trajectory at radius $\mathfrak{R}$, the two equations above can be combined into:

$$\frac{B_\phi}{B_p} = \frac{(\omega - \omega_K)}{V_p} \mathfrak{R} = \frac{\omega_e}{V_p} \mathfrak{R} \quad (\text{D.3})$$

where we have used the definition of ω_e in Eq. 6. We can define the magnetic field helix angle $\alpha_B = \arctan(B_\phi/B_p)$, which is the angle with which a helical field line winds around the jet axis.

We have seen that the observation of well defined sinusoids in the plane of the sky requires that the rotation radius $\mathfrak{R}$, and the ratio of the effective angular velocity ω_e on the streaming velocity V_z keep constant (see Eq. 7). Since the poloidal velocity V_p is equal to V_z if $\mathfrak{R}$ is constant, Eq. D.3 implies that α_B does not vary along each of the observed maser streams. However, the reverse argument holds too. If the magnetic field is sufficiently stable and has a constant helix angle (that is, a helical configuration), the motion along the field line (in the co-rotating reference frame) requires a constant value of the ratio ω_e/V_z . That preserves the maser sinusoidal pattern despite the concomitant presence of a relatively large velocity scatter. From Eqs. D.3 and 7, with $V_p = V_z$, we have:

$$\frac{|B_\phi|}{B_p} = f_z \mathfrak{R} \quad (\text{D.4})$$

Using the values reported in Table 1, we derive: $f_z \mathfrak{R} = 0.79 \pm 0.06$, 1.1 ± 0.2 , 0.88 ± 0.04 , and 0.70 ± 0.05 for the SW, NE-1, NE-2 and NE-3 streams, respectively. From Eq. D.2, $B_\phi \approx 0$ within the Alfvén point when the flow co-rotates with the disk and $V_\phi \approx \omega_K \mathfrak{R}$. Beyond the Alfvén point, the inertia of the matter in the flow forces the magnetic field to fall behind the rotation of the disk, which causes $|B_\phi|$ to increase. The derived values of the ratio $|B_\phi|/B_p$ in the range 0.7–1.1 agree with the water masers tracing a region of the spiraling trajectory in between the Alfvén point and the fast magneto-sonic point, beyond which the toroidal magnetic field component should become the predominant component^{34,38}.

Finally, we discuss briefly possible causes for the observed velocity scatter. For the SW, NE-1, and NE-2 spiral motions, the residual of the linear fit of V_{LSR} versus R is plotted versus z in Fig. D.1. These plots indicate that the residual velocity is not correlated with position, contrarily to what it would be expected if the velocity scatter from the linear fit was caused by the smooth change with z of the characteristic velocities, ω and V_z (and consequently V_{off}), of the spiraling trajectory. The residual velocities cannot be dominated by turbulence, too, since the latter would produce an independent variation of the toroidal and poloidal velocity components, which, as discussed above, is not consistent with the observation of the maser sinusoidal patterns. Moreover, it would be difficult to explain the observed different degree of turbulence between the NE-1 and NE-2 streams (see Fig. D.1) over the same region of the sky.

The irregular change of the velocities can be naturally linked to our flow tracers, the water masers, which are excited in internal shocks of the flow emerging from perturbed locations of the disk. Eq. D.1 and D.2 show that the flow velocity depends critically on the mass load k , which, on its turn, depends on the physical conditions, including dissipative processes, near the disk surface. If the physical conditions of the perturbed launch points




Fig. D.1. Maser velocity scatter. The residual velocity from the linear fit of maser V_{LSR} versus R (see Figs. 4b and 5b) is plotted versus $|z|$ for the masers in the SW (upper panel), NE-1 (central panel), and NE-2 (lower panel) streams.

varied erratically on time scales so short as months, that would qualitatively explain the observed scatter of maser velocities. Emission variability over time scales of months is observed and theoretically expected in accretion bursts from high-mass YSOs^{6,11,28}, in such cases where an extended portion of the accretion disk gets perturbed.

Appendix E: Water masers: shock type and corresponding flow kinematics

We propose that the water masers observed in IRAS 21078+5211 inside the NE, SW and N regions arise in internal shocks along streamlines of the YSO’s disk wind. If observed at sufficiently high angular resolution, radio jets are often resolved into chains of compact emission centers (named “knots”), which are interpreted in terms of internal shocks owing to fluctuation in mass or velocity ejection². Since the jets are the innermost (most collimated and fastest) portion of a disk wind, it is possible that the structure of more external streamlines, where the gas is weakly ionized and mainly molecular, is characterized by internal shocks, too. If the fluctuation responsible for the shocks is relatively small compared to the (time average) flow properties, the internal shocks are weak C-shocks and the shock (and maser) velocity is close to the flow velocity. In fact, the proper motions of radio knots are considered a reliable measurement of the jet speed². In IRAS 21078+5211, the

regular (arc-like) spatial and V_{LSR} distribution of the water masers indicate that the masers co-move with the flowing gas.

Models of water maser excitation predict them to arise in both strong dissociative $\text{J}^{7,10}$ - and weak non-dissociative C^{12} -shocks. While in J-shocks the masers form in the cooling post-shock gas at $T_{\text{kin}} \approx 400$ K following the chemical re-formation of water, in C-shocks the masing molecules do not dissociate and reach a significantly higher temperature, $T_{\text{kin}} \approx 1000\text{--}3000$ K. The presence of shocks is naturally expected in correspondence of the fast protostellar outflows, whose association with the 22 GHz water masers is well proved observationally²⁵. The location of the 22 GHz masers, often found at the wall of the jet cavity or at the terminal bow-shock of the jet, and their speed (mainly $\leq 30 \text{ km s}^{-1}$)²⁶ significantly smaller than that of the jet (a few 100 km s^{-1})², indicate that the large majority of the 22 GHz water masers arise in strong external (lateral or terminal) J-shocks of the fast flow against the dense ambient material. While the velocity of the internal shocks is close to the flow speed, external shocks travel at a reduced speed because of the density contrast between the lighter impinging flow and the denser surrounding material.

As exemplified by our observations in IRAS 21078+5211, the origin of the 22 GHz masers in internal shocks of the flow make them a formidable tool to trace individual streams of gas of the disk wind. In the following, we show that the alternative interpretation for these masers as external shocks of a wide-angle wind or a jet impacting against the surrounding medium is much less plausible. Looking at Fig. 2a, the water masers could be found at the wall of a wind cavity, if the axis of this putative wind was oriented at $\text{PA} \approx 10^\circ\text{--}20^\circ$ and its opening angle was $\approx 30^\circ\text{--}40^\circ$. It is very difficult to conciliate this wide-angle wind with the jet geometry and precession rate estimated from previous (2010–2013) JVLBA and VLBA observations (see Fig. 1). The elongation ($\text{PA} = 56^\circ \pm 12^\circ$) of the slightly resolved (size ≈ 150 au) JVLBA continuum at 1.3 cm, the collimated ($\text{PA} = 49^\circ \pm 18^\circ$) proper motions of the water masers near (100–200 au) the YSO, and the direction ($\text{PA} \approx 44^\circ$) of the non-thermal radio jet traced by the extended (size ≈ 1000 au) JVLBA continuum at 5 cm, consistently indicate the presence of a jet oriented at $\text{PA} \approx 50^\circ$. A distinct signature of precession²⁶ was the finding of a spur in the 5 cm continuum ≈ 7000 au NE from the YSO along the same direction, $\text{PA} = 60^\circ$, of the red-shifted lobe of the SO outflow observed with NOEMA. Clearly, a precession rate of only $\approx (60^\circ - 50^\circ) = 10^\circ$ over a length scale of 7000 au cannot account for a change in orientation between the putative wind and the JVLBA/VLBA jet of $\geq (50^\circ - 20^\circ) = 30^\circ$ over a length scale ≤ 100 au and a timescale ≤ 10 yr. On the other hand, if this inner wind and the jet co-existed, it would be even more difficult to explain an abrupt transition in orientation and opening angle from the former to the latter across a few 10 au (see Fig. 2a). The interpretation of the water masers in IRAS 21078+5211 as external shocks at the cavity wall of a wide-angle wind faces also the difficulty to account for the huge maser V_{LSR} gradients, $\geq 40 \text{ km s}^{-1}$ over ≤ 10 au,

transversal to the NE stream at elevation $z \geq 90$ au (see Fig. 5a). If the masers, instead of delineating two streams at different velocities, traced shock fronts (seen close to edge-on) at the wind wall, it would be very difficult to explain such a large velocity difference for almost overlapping emissions.

We conclude this discussion on alternatives to the disk wind interpretation showing that it is improbable that we are observing multiple outflows from a binary system. Inspecting Fig. 1, our previous NOEMA/JVLA/VLBA observations consistently indicate a single disk/jet system on scales of 100–500 au. The NOEMA 1.37 mm and the JVLA 1.3 cm continuum emissions, tracing the hosting molecular core and YSO’s ionization, respectively, are compact and well aligned in position. The rotating disk revealed by the V_{LSR} gradient of high-density molecular (CH_3CN and HC_3N) lines is centered on the peak of the 1.3 cm continuum. The agreement in direction between the elongated (double-lobe) JVLA 5 cm continuum and the collimated water maser proper motions points to a single jet emerging from the YSO. Considering now the new, global VLBI observations, on scales of 1–100 au, Fig. 2a shows that the spatial distribution of the water masers is about symmetrical with respect to the YSO position. This further supports the interpretation that a single YSO is responsible for the excitation and motion of the water masers.

Appendix F: Constraining the Alfvén point of the NE-1 stream

Fig. F.1 shows that the V_{LSR} of the five masers at the base ($z \approx 20$ au) of the NE-1 stream (inside the dashed rectangle of Fig. 5a) changes linearly with R . The derived value of $\omega = 1.82 \pm 0.09 \text{ km s}^{-1} \text{ au}^{-1}$ is significantly higher than the value, $1.15 \pm 0.09 \text{ km s}^{-1} \text{ au}^{-1}$ (see Table 1), determined at larger elevations. That can be interpreted as evidence that the gas closer to the Alfvén point rotates faster than that at higher elevations, in agreement with the MHD disk-wind theory. As described in Appendix A, each maser feature is a collection of many compact spots for which we have accurately measured position and V_{LSR} . For the maser feature (out of the five) nearest to the jet axis, Fig. F.2a shows that the spatial distribution of the spots is linear and elongated close to (7° away from) the disk axis, and Fig. F.2b shows that the spot V_{LSR} changes linearly with the position, ΔR , along the major axis of the spatial distribution. Given its orientation, it is natural to interpret the V_{LSR} gradient internal to the maser feature in terms of rotation, and from the linear fit of V_{LSR} versus ΔR we derive a value of $\omega = 2.3 \pm 0.1 \text{ km s}^{-1} \text{ au}^{-1}$. This should still be considered a lower limit for ω_K , the angular velocity at the Alfvén point. Beside the one just considered, other two maser features present a well defined, internal V_{LSR} gradient. In these two features, the linear distribution of the spots is directed at larger angles, $20\text{--}30^\circ$, from the disk axis, and the amplitudes of the V_{LSR} gradients are 1.8 ± 0.1 and $3.1 \pm 0.1 \text{ km s}^{-1} \text{ au}^{-1}$. These two features have larger separation from the jet axis and the corresponding larger inclination of the spot distribution with the plane of rotation




Fig. F.1. Estimate of ω at the base of the NE-1 stream. Plot of V_{LSR} versus R for the maser cluster at the base of the NE-1 stream, inside the dashed rectangle in Fig. 5a. Vertical black and horizontal red errorbars indicate velocities and radii (with corresponding errors), respectively. The black dashed and dotted lines show the best linear fit and the associated uncertainty, respectively.

could indicate that the internal V_{LSR} gradient is influenced by non-rotation terms, as, for instance, the increase of the streaming velocity with the elevation. In any case, assuming that also for these two features the internal V_{LSR} gradient is dominated by rotation, we obtain a consistent average value for the in-feature angular velocity of $\omega = 2.4 \text{ km s}^{-1} \text{ au}^{-1}$.

We stress that the internal motion of the maser features does not contribute to the features' V_{LSR} used in our analysis of the maser velocity pattern on larger scales (see Figs. 4, 5 and 6). In fact, the feature V_{LSR} is obtained by averaging the internal spots' V_{LSR} (see Appendix A), with the result that any contribution from internal motions is averaged out. In the previous analysis, we have interpreted the maser internal motions, on scales of a few au, as a product of the larger scale (10–100 au) motions. Since we have considered only five features within a small area, this interpretation has to be better justified. Fig. F.3 shows the internal gradient orientation for all the maser features in IRAS 21078+5211 with well defined internal gradients. Most of the gradients are directed close to either the jet or disk axis. That suggests that the maser internal motions trace mainly the large scale dynamics, dominated by either the streaming flow motion or rotation. Interestingly, a previous study²³ of a sample of 6.7 GHz methanol maser sources reached a similar conclusion. Finally, we note that, on the size (a few au) of the maser features, turbulent motions have to be significantly smaller than the typical maser line widths or $\leq 0.1 \text{ km s}^{-1}$, otherwise they would destroy the velocity coherence along the maser amplification path.




Fig. F.2. Rotation inside individual maser features. (a) Colored errorbars give positions (and corresponding errors) of the individual spots collected into the maser feature, with colors denoting the maser V_{LSR} . The black continuous and dashed lines give the best linear fit of the spot positions and the associated uncertainty, respectively. (b) Plot of the spot V_{LSR} versus positions projected along the major axis of the spot distribution. The black continuous and dashed lines show the best linear fit of the plotted values and the associated uncertainty, respectively.

Appendix G: Kinematics of the water masers further to NE and S

In the main text, we have considered only the filaments of maser emission inside the NE, SW and N regions, but more scattered maser features are also observed further to NE close to the jet axis and S of the YSO (see Fig. 2a). The outmost northeastern features are found approximately in the same region of the previous VLBA maser detections (see Fig. 2a). However the newly observed masers are fewer than before and their V_{LSR} is now within $\pm 5 \text{ km s}^{-1}$ from V_{sys} instead of covering the range $[-38, 0] \text{ km s}^{-1}$ as before. The directions of the VLBA maser proper motions are well collimated but their amplitudes (in the range $[10, 50] \text{ km s}^{-1}$) scatter significantly in position (see Fig. 1b), which, as discussed in Appendix E, suggests that these masers arise in external shocks and do not trace the true flow speed. In our previous analysis²⁶, we have interpreted these outmost northeastern masers as external shocks at the wall of a cylindrical MHD jet interacting with the surrounding medium. Applying the equations for a MHD disk wind, we have derived a terminal jet speed of $\approx 200 \text{ km s}^{-1}$ and a launch radius of $\approx 2 \text{ au}$. These values agree with the trend of the calculations reported in Table 2, where higher streaming velocities correspond to smaller launch radii.

The southern features are distributed in three separated clusters (see Fig. 2a): C1) $z \leq 20 \text{ au}$ and $9.5 \text{ km s}^{-1} \leq V_{\text{LSR}} \leq 17.4 \text{ km s}^{-1}$; C2) $20 \leq z \leq 100 \text{ au}$ and $5.5 \text{ km s}^{-1} \leq V_{\text{LSR}} \leq 9.5 \text{ km s}^{-1}$; C3) $z \geq 120 \text{ au}$ and $5.5 \text{ km s}^{-1} \leq V_{\text{LSR}} \leq 29.7 \text{ km s}^{-1}$. Comparing




Fig. F.3. Spatial distribution of internal velocity gradients of 22 GHz water maser features. Colored dots, black dotted rectangles, and the red and black dashed lines have the same meaning as in Fig. 2a. The black segments show the velocity gradient orientation. Only the maser features which yield correlation coefficients ≥ 0.7 from the linear fits of both the spot positions (see Fig. F.2a) and V_{LSR} versus projected positions (see Fig. F.2b), are plotted.

the C1 & C2 clusters with the N region, maser positions and V_{LSR} are about symmetrical with respect to the YSO; beside, each of the two clusters presents an arc-like shape similar to the N streamline. Thus, it is possible that these clusters trace small portions of two co-rotating streamlines emerging at different disk radii. Finally, the maser cluster C3 has position and V_{LSR} approximately symmetrical to the emission previously observed with the VLBA further to NE (see Fig. 1b), which suggests that masers in C3 can emerge in shocks at the wall of the southeastern lobe of the jet.

Appendix H: Simulation snapshot of a forming massive star

As part of a more extensive study we will describe in a forthcoming article, we performed an axisymmetrical simulation of the formation of a massive star starting from the gravitational collapse of a rotating cloud core threaded by a magnetic field (GAO, RK et al., in preparation). We used the methods of magnetohydrodynamics to model the weakly ionized gas and dust with the code Pluto²⁰, with an Ohmic resistivity model as a non-ideal effect¹⁸, and additional modules for self-gravity¹⁵ and the transport of the thermal radiation emitted by the gas and dust¹⁶.

The cloud core has an initial mass of $100 M_{\odot}$ and a radius of 0.1 pc . The assumed conditions for the onset of the gravitational collapse ($t = 0$) are as follows: the density is distributed according to $\rho \propto r^{-1.5}$, the cloud core rotates like a solid body with a rotational energy equivalent to 4% of its gravitational energy content, and the magnetic field is uniform. The initial magnitude of the magnetic field is determined by the mass-to-flux




Fig. H.1. Simulation snapshot of a forming massive star, surrounded by an accretion disk and magnetically-driven outflows. (a) Density, velocity and magnetic field lines. (b) Contours that show the regions where: the material is sub-Alfvénic (yellow), the magnetic field lines are wound by rotation (purple), and the centrifugal acceleration is stronger than gravity (blue). The shadow that accompanies each contour indicates the region where the inequality listed in the legend holds true. The contour lines have been smoothened in order to filter out local and short-lived features. (c) Large-scale structure of the outflows. (d) Bow-shock produced in the simulation.

ratio, which we take as 20 times the critical (collapse-preventing) value²⁷ and corresponds to a relatively weak initial magnetic field. A constant value of the opacity of $1 \text{ cm}^2 \text{ g}^{-1}$ was used to model the gas and dust, as well as an initial dust-to-gas mass ratio of 1%.

We used an axisymmetrical grid of 896×160 cells in spherical coordinates, with the radial coordinate increasing logarithmically with the distance to the center of the cloud. An inner boundary of 3 au was set up, inside of which the protostar is formed through accretion. No flows are artificially injected from the inner boundary into the collapsing cloud.

The simulation starts with an initial gravitational collapse epoch. After ~ 5 kyr, enough angular momentum is transported to the center of the cloud to start forming an accretion disk that grows in size over time. Roughly at the same time, we observe the launch of magnetically-driven outflows. Magnetic pressure arising from the dragging of magnetic field lines by the rotating flow eventually overcomes gravity and seeds the formation of the outflow cavity, thrusting a bow shock in the process (Fig. H.1d), which propagates outwards as the cavity grows in size. Previous observations of IRAS 21078+5211 have uncovered the presence of a bow shock located at distances of ≈ 36000 au from the forming massive YSO²⁶. The initial launch of the magnetically-driven outflows provides a possible formation mechanism for the observed bow shock and in return, the propagation of the bow shock provides an estimation for the age of the system.

In the simulation, the protostar reaches a mass of $5.24 M_{\odot}$ (a value in the expected mass interval from observations) after 13.84 kyr of evolution. We estimate that the bow shock has propagated to a distance of ≈ 30000 au at that time, roughly in line with the observations. At the same time, the accretion disk has grown to about 180 au in radius, in agreement with the observational estimates²⁶, as well. The data reveal a magneto-centrifugally launched jet, in a similar way as reported by the literature^{4,13}, however, we see that the launching region of the jet is narrowed by the ram pressure of the infalling material from the envelope and the presence of a thick layer of the accretion disk which is vertically supported by magnetic pressure. Material transported from large scales through the accretion disk reaches the launching region, located at $z \lesssim 100$ au (see Fig. H.1b), where the centrifugal force is stronger than gravity, and simultaneously, where the flow becomes sub-Alfvénic in the co-rotating frame and the magnetic field lines are mostly poloidal. Under those conditions, a parcel of plasma is accelerated along the field lines until the flow becomes super-Alfvénic again, a point at which the magnetic field lines become mostly toroidal. This causes the parcel to acquire a helical trajectory (depicted previously in Fig. 2b). The geometry and kinematics of the region where the flow becomes helical in the simulation coincides roughly with the positions and velocities of the observed masers of the NE and SW regions. At larger rotation radii, the broader magnetic field lines present in the outflow cavity could give rise to the kinematic footprint detected in the masers in the N region.

At distances of ~ 10000 au, where the outflow material propagates through the cloud (Fig. H.1c), we notice the existence of re-collimation zones that arise because of magnetic hoop stress and ram pressure from the envelope. The position of the re-collimation zones is similar to the zones where lobes of possible synchrotron emission have been previously observed around the YSO²⁶, thus providing a possible mechanism for their formation.

We provide this comparison as an example that a magneto-centrifugally launched jet around a forming massive star yields a consistent picture with the observations. However, the coincidences should be taken with caution, as different combinations of initial conditions may yield similar results, which means that a wider and deeper investigation is needed in order to determine the conditions of the onset of star formation from the observational data.

Correspondence and Request for Material:

Any request should be addressed to Luca Moscadelli

Data Availability:

This letter makes use of the following EVN data: GM077 (EVN project code).

The datasets generated during and/or analyzed during the current study are available from the corresponding author on reasonable request.

Author Contribution Statement:

L.M. led the project, analysis, discussion, and drafted the manuscript.

A.S, H.B., and R.K. commented on the manuscript and participated in the discussion.

G.A.O. and R.K. performed the numerical jet simulations described in Appendix H.

G.A.O. performed the dynamical analysis of the simulations, compared the simulation results to the observations, and produced the illustrations of the magnetic field lines and streamlines.

Competing Interests:

The authors declare no competing (financial and non-financial) interests.

Table A.3. 22.2 GHz H₂O maser parameters for IRAS 21078+5211

Feature Number	I _{peak} (Jy beam ⁻¹)	V _{LSR} (km s ⁻¹)	Δ <i>x</i> (mas)	Δ <i>y</i> (mas)
1	53.066	-21.6	0	0
2	14.326	-3.0	60.42±0.03	27.87±0.03
3	14.017	-24.0	-14.93±0.03	51.87±0.03
4	10.457	-28.5	-1.55±0.03	58.23±0.03
5	7.082	0.4	-42.37±0.03	-36.16±0.03
6	6.565	-1.0	56.89±0.03	18.87±0.03
7	6.502	-15.2	23.06±0.03	-4.24±0.03
8	5.543	-30.2	-1.29±0.03	59.10±0.03
9	4.904	-21.8	0.07±0.03	0.46±0.03
10	4.866	-15.1	33.59±0.03	3.34±0.03
11	4.812	-19.8	58.57±0.03	32.40±0.03
12	4.395	-24.8	-14.78±0.03	52.52±0.03
13	4.273	5.0	-43.75±0.03	-40.90±0.03
14	4.072	-3.2	60.79±0.03	28.54±0.03
15	3.556	-25.2	14.57±0.03	-3.37±0.03
16	3.397	1.5	61.14±0.03	31.34±0.03
17	3.387	-0.1	-41.84±0.03	-34.58±0.03
18	3.206	-15.4	33.76±0.03	3.88±0.03
19	3.177	-22.7	-11.28±0.03	22.53±0.03
20	2.485	-11.7	53.03±0.03	19.32±0.03
21	2.391	-17.3	29.96±0.03	-0.05±0.03
22	2.247	-2.1	59.06±0.03	22.92±0.03
23	2.154	-24.1	-15.03±0.03	51.42±0.03
24	2.072	4.3	-44.37±0.03	-39.19±0.03
25	2.062	-16.2	25.54±0.03	-3.08±0.03
26	1.952	4.5	-45.06±0.03	-41.80±0.03
27	1.926	-6.2	60.50±0.03	38.38±0.03
28	1.740	-27.4	-11.03±0.03	22.50±0.03
29	1.661	-37.8	55.01±0.03	33.58±0.03
30	1.631	-10.8	62.36±0.03	37.98±0.03
31	1.537	5.2	-43.54±0.03	-40.37±0.03
32	1.420	-27.5	121.15±0.03	120.88±0.03
33	1.137	-2.0	57.72±0.03	20.15±0.03
34	1.109	17.1	-11.32±0.03	-16.69±0.03

Table A.3. continued.

Feature Number	I_{peak} (Jy beam ⁻¹)	V_{LSR} (km s ⁻¹)	Δx (mas)	Δy (mas)
35	0.986	-1.6	58.65±0.03	22.43±0.03
36	0.954	-8.1	61.04±0.03	38.18±0.03
37	0.866	-13.6	21.30±0.03	-5.56±0.03
38	0.859	-9.5	44.93±0.03	10.49±0.03
39	0.774	-16.5	23.77±0.03	-3.55±0.03
40	0.756	0.4	59.72±0.03	27.76±0.03
41	0.745	-10.7	44.31±0.03	10.40±0.03
42	0.678	-22.7	14.29±0.03	-4.41±0.03
43	0.649	-8.9	120.25±0.03	100.23±0.03
44	0.554	-0.0	-42.04±0.03	-35.56±0.03
45	0.539	-30.3	-1.21±0.03	59.56±0.03
46	0.512	6.7	-57.34±0.03	-138.41±0.03
47	0.428	-8.9	44.04±0.03	9.57±0.03
48	0.375	-25.2	14.07±0.03	-3.40±0.03
49	0.374	-15.8	34.29±0.03	4.60±0.03
50	0.367	-23.3	14.55±0.03	-3.95±0.03
51	0.364	-4.3	60.56±0.03	30.64±0.03
52	0.358	-9.1	61.21±0.03	37.42±0.03
53	0.352	-18.1	118.48±0.03	99.46±0.03
54	0.339	-31.6	55.84±0.03	40.17±0.03
55	0.290	-8.5	121.39±0.03	100.59±0.03
56	0.270	-1.7	58.08±0.03	21.15±0.03
57	0.268	-3.5	138.43±0.03	90.24±0.03
58	0.266	-17.4	29.50±0.03	-0.42±0.03
59	0.259	-10.0	43.61±0.03	9.66±0.03
60	0.228	-25.8	-8.48±0.03	57.46±0.03
61	0.213	-30.6	55.99±0.03	39.54±0.03
62	0.200	-16.9	33.88±0.03	4.64±0.03
63	0.200	-12.2	21.80±0.03	-5.36±0.03
64	0.199	-10.1	62.03±0.03	38.42±0.03
65	0.195	-15.6	33.15±0.03	2.76±0.03
66	0.191	4.4	-45.46±0.03	-42.22±0.03
67	0.185	-16.5	24.85±0.03	-3.22±0.03
68	0.181	-8.5	124.31±0.03	100.94±0.03

Table A.3. continued.

Feature Number	I_{peak} (Jy beam $^{-1}$)	V_{LSR} (km s $^{-1}$)	Δx (mas)	Δy (mas)
69	0.178	0.5	-40.76 $\pm$ 0.03	-32.20 $\pm$ 0.03
70	0.170	-12.1	34.87 $\pm$ 0.03	5.95 $\pm$ 0.03
71	0.164	-1.2	60.11 $\pm$ 0.03	34.24 $\pm$ 0.03
72	0.161	-13.0	59.54 $\pm$ 0.03	29.23 $\pm$ 0.03
73	0.161	-1.9	61.56 $\pm$ 0.03	32.23 $\pm$ 0.03
74	0.161	-8.4	122.16 $\pm$ 0.03	100.72 $\pm$ 0.03
75	0.155	-19.9	58.58 $\pm$ 0.03	31.90 $\pm$ 0.03
76	0.155	-33.7	55.96 $\pm$ 0.03	37.71 $\pm$ 0.03
77	0.152	1.0	58.10 $\pm$ 0.03	23.42 $\pm$ 0.04
78	0.145	2.0	-42.80 $\pm$ 0.03	-37.01 $\pm$ 0.03
79	0.138	-27.5	-10.99 $\pm$ 0.03	22.85 $\pm$ 0.03
80	0.132	-26.0	30.09 $\pm$ 0.03	0.66 $\pm$ 0.03
81	0.127	-13.4	62.41 $\pm$ 0.03	36.36 $\pm$ 0.03
82	0.121	6.8	38.38 $\pm$ 0.03	-105.32 $\pm$ 0.03
83	0.107	-20.4	14.92 $\pm$ 0.05	-5.16 $\pm$ 0.05
84	0.105	-12.1	58.11 $\pm$ 0.03	25.16 $\pm$ 0.03
85	0.102	-1.0	61.01 $\pm$ 0.03	30.58 $\pm$ 0.04
86	0.101	-18.0	65.66 $\pm$ 0.03	36.02 $\pm$ 0.03
87	0.099	-18.6	-4.44 $\pm$ 0.03	57.01 $\pm$ 0.03
88	0.097	-23.5	-15.53 $\pm$ 0.03	49.39 $\pm$ 0.03
89	0.096	1.6	57.02 $\pm$ 0.03	21.67 $\pm$ 0.03
90	0.094	-1.2	-44.13 $\pm$ 0.03	-38.22 $\pm$ 0.03
91	0.094	2.9	60.86 $\pm$ 0.03	30.86 $\pm$ 0.03
92	0.093	5.7	-42.83 $\pm$ 0.03	-39.80 $\pm$ 0.03
93	0.091	-34.2	-12.84 $\pm$ 0.03	51.09 $\pm$ 0.03
94	0.074	-26.3	-11.14 $\pm$ 0.03	22.22 $\pm$ 0.03
95	0.069	-18.4	30.26 $\pm$ 0.03	0.51 $\pm$ 0.03
96	0.069	-8.3	127.68 $\pm$ 0.03	100.86 $\pm$ 0.03
97	0.067	-0.2	-40.55 $\pm$ 0.05	-31.83 $\pm$ 0.04
98	0.065	0.0	58.01 $\pm$ 0.04	21.83 $\pm$ 0.05
99	0.065	-18.2	-12.24 $\pm$ 0.03	22.63 $\pm$ 0.03
100	0.064	-17.9	-20.70 $\pm$ 0.03	26.63 $\pm$ 0.03
101	0.064	-19.8	-22.59 $\pm$ 0.03	32.39 $\pm$ 0.03
102	0.063	-10.9	62.10 $\pm$ 0.03	37.24 $\pm$ 0.03

Table A.3. continued.

Feature Number	I_{peak} (Jy beam $^{-1}$)	V_{LSR} (km s $^{-1}$)	Δx (mas)	Δy (mas)
103	0.062	-10.6	35.68 $\pm$ 0.03	8.84 $\pm$ 0.03
104	0.061	17.0	-11.54 $\pm$ 0.03	-16.91 $\pm$ 0.03
105	0.060	-14.3	41.60 $\pm$ 0.03	10.24 $\pm$ 0.03
106	0.056	9.1	-45.72 $\pm$ 0.03	-44.04 $\pm$ 0.03
107	0.051	-0.9	-21.86 $\pm$ 0.05	-17.36 $\pm$ 0.04
108	0.049	-9.9	37.06 $\pm$ 0.03	7.68 $\pm$ 0.03
109	0.048	-14.7	59.47 $\pm$ 0.03	28.61 $\pm$ 0.03
110	0.048	2.7	58.82 $\pm$ 0.03	25.55 $\pm$ 0.03
111	0.047	-12.2	59.77 $\pm$ 0.03	29.64 $\pm$ 0.03
112	0.046	-12.5	43.30 $\pm$ 0.03	11.05 $\pm$ 0.03
113	0.046	-8.3	-41.69 $\pm$ 0.03	-23.95 $\pm$ 0.03
114	0.044	-12.5	62.24 $\pm$ 0.03	35.91 $\pm$ 0.03
115	0.044	-1.1	-23.09 $\pm$ 0.06	-18.46 $\pm$ 0.05
116	0.043	-16.0	59.12 $\pm$ 0.04	27.70 $\pm$ 0.04
117	0.043	-33.2	-13.02 $\pm$ 0.03	50.88 $\pm$ 0.03
118	0.041	11.6	12.77 $\pm$ 0.03	-29.04 $\pm$ 0.03
119	0.040	10.5	12.91 $\pm$ 0.03	-27.04 $\pm$ 0.03
120	0.039	-11.5	44.63 $\pm$ 0.03	10.64 $\pm$ 0.03
121	0.039	-7.7	36.05 $\pm$ 0.03	7.54 $\pm$ 0.03
122	0.036	-5.9	60.39 $\pm$ 0.03	37.90 $\pm$ 0.03
123	0.036	11.0	-50.13 $\pm$ 0.03	-135.02 $\pm$ 0.03
124	0.033	-27.4	121.11 $\pm$ 0.04	120.44 $\pm$ 0.03
125	0.032	-18.4	-21.05 $\pm$ 0.03	27.82 $\pm$ 0.03
126	0.032	3.6	-43.27 $\pm$ 0.03	-38.14 $\pm$ 0.04
127	0.032	-31.6	56.14 $\pm$ 0.03	40.39 $\pm$ 0.03
128	0.030	-29.4	54.79 $\pm$ 0.03	35.16 $\pm$ 0.03
129	0.029	-10.8	46.33 $\pm$ 0.04	11.49 $\pm$ 0.03
130	0.029	-20.1	-22.18 $\pm$ 0.04	37.50 $\pm$ 0.04
131	0.027	9.7	-59.68 $\pm$ 0.03	-137.27 $\pm$ 0.03
132	0.025	-5.8	110.29 $\pm$ 0.04	56.94 $\pm$ 0.04
133	0.022	-14.1	34.57 $\pm$ 0.04	5.08 $\pm$ 0.04
134	0.021	5.9	-42.25 $\pm$ 0.03	-39.12 $\pm$ 0.03
135	0.020	-29.4	56.24 $\pm$ 0.04	35.30 $\pm$ 0.04
136	0.019	10.9	13.38 $\pm$ 0.04	-27.78 $\pm$ 0.04

Table A.3. continued.

Feature Number	I_{peak} (Jy beam ⁻¹)	V_{LSR} (km s ⁻¹)	Δx (mas)	Δy (mas)
137	0.019	-18.3	24.24±0.04	-3.28±0.04
138	0.018	10.8	-59.98±0.04	-136.68±0.04
139	0.017	29.3	-59.75±0.03	-120.52±0.03
140	0.017	-5.8	108.81±0.05	57.04±0.05
141	0.017	-18.3	118.43±0.05	98.90±0.04
142	0.016	-31.0	64.36±0.04	45.69±0.05
143	0.015	-7.6	134.19±0.04	91.17±0.04
144	0.015	19.2	-48.27±0.04	-55.22±0.04
145	0.013	7.3	34.56±0.04	-116.70±0.04
146	0.013	-12.7	39.14±0.05	9.70±0.05
147	0.012	-8.8	119.61±0.05	100.15±0.05
148	0.011	13.5	11.24±0.04	-30.82±0.04
149	0.011	-33.5	-13.27±0.04	50.41±0.04
150	0.011	10.4	12.78±0.04	-26.19±0.04
151	0.011	-5.5	111.16±0.05	56.61±0.05
152	0.011	19.0	-60.91±0.04	-124.10±0.04
153	0.010	13.4	12.64±0.04	-32.15±0.04
154	0.010	-5.3	140.28±0.05	33.19±0.05
155	0.010	-31.7	1.13±0.04	61.26±0.04
156	0.009	17.9	-63.61±0.05	-124.63±0.05
157	0.009	-7.6	123.27±0.06	101.80±0.05
158	0.009	-18.7	-21.77±0.06	29.92±0.05
159	0.008	8.6	33.57±0.05	-119.04±0.05
160	0.008	-33.0	-12.72±0.05	51.44±0.05
161	0.008	-5.4	83.67±0.06	45.45±0.07
162	0.008	-9.1	98.09±0.09	68.97±0.08
163	0.007	-39.6	140.57±0.06	213.71±0.06
164	0.007	-37.1	139.82±0.06	214.08±0.06
165	0.006	11.9	13.04±0.06	-29.94±0.05
166	0.006	8.6	40.93±0.06	-85.43±0.07
167	0.006	10.3	-62.68±0.08	-66.21±0.06
168	0.005	12.5	-45.00±0.06	-44.03±0.05

Notes.

Column 1 gives the feature label number; Cols. 2 and 3 provide the intensity of the strongest spot and the intensity-weighted spots' V_{LSR} , respectively; Cols. 4 and 5 give the position offsets (with the associated errors) towards East and North, respectively, relative to feature # 1.

The absolute position of feature # 1 is: R.A. (J2000) = $21^{\text{h}} 9^{\text{m}} 21^{\text{s}}.7099$, Dec (J2000) = $52^{\circ} 22' 37''.001$. The absolute position is evaluated at the observing epoch: October 27, 2020.